

BODY TYPE: EXTRUDED ALUMINUM  
TANK SIDE: WET SIDE

DOC. NO. : E018-1 DRAWING TEMPLATE  
REV. C 2017-02-05

**SPECIFICATION**

**CHASSIS:**  
-FREIGHTLINER M2 106 SBA REGULAR CAB  
-49,000 LB GVWR; 18,000 LB FRONT / 31,000 LB REAR  
-DIESEL ENGINE, CUMMINS L9 350 EV HP  
-AUTOMATIC TRANSMISSION, ALLISON 3000 EVS

**PUMP:**  
-HALE MODULE SIDEKICK 750 GPM MBP  
-750 USGPM (2839 LPM) (624 IGPM) AT 150PSI  
-THIRD PARTY CERTIFICATION MEETING NFPA1901-2016

**PLUMBING AND PIPING: STAINLESS STEEL SCHEDULE 10**  
- 2 x 5" MAIN SUCTION, (1)ROAD (1)CURB  
- 1 x 2 1/2" GATED SUCTION, (1)ROAD  
- 2 x 1 1/2" SPEEDLAY'S - HOSE BED PRECONNECT  
- 3 x 2 1/2" DISCHARGE, (3)ROAD  
- 1 x 1" HOSE REEL PLUMBING  
- 1 x 2 1/2" EXTERNAL TANK FILL FIREMAN'S FRIEND  
- 4" TANK TO PUMP, 4" BUTTERFLY VALVE - AIR  
- 2" TANK FILL

**TANK:**  
-2000 USG WATER TANK



**BODY:**  
-WET SIDE FIRE TANKER, EXTRUDED ALUMINUM LOW/LOW  
-BODY UNDERCOATING CORASHIELD

**EMERGENCY EQUIPMENT/ACCESSORIES:**

SEE QUOTE SPECIFICATION FOR DETAILS

COMPT.	COMPARTMENT FRAME DIMENSIONS
L1	74W x 40H x 13.5/26D
L2	36W x 40H x 13.5/26D
R1	74W x 40H x 13.5/26D
R2	36W x 40H x 13.5/26D

1. THE DRAWING IS FOR REFERENCE PURPOSE, ONLY. THE DRAWING MAY OR MAY NOT SHOW ALL ITEMS AS DESCRIBED IN THE WRITTEN DETAILED SPECIFICATION.
2. INCLUSION OF AN ITEM ON THE DRAWING DOES NOT CONSTITUTE INCLUSION OF THAT ITEM WITH THE FINAL DELIVERY OF THE UNIT. SPECIFICATION SHALL BE FINAL AUTHORITY TO BE DETERMINED WHAT IS SUPPLIED ON THE APPARATUS.
3. THE EFFECTIVE DOOR OPENING FOR ROLLUP DOORS WILL BE REDUCED APPROX. 10" IN HEIGHT, 2" IN DEPTH AND 2" IN WIDTH FROM SHOWN FRAME OPENINGS AND 2" IN HEIGHT, 3" IN DEPTH AND UP TO 4" IN WIDTH FOR PAN DOORS. DIMENSIONS TOLERANCE ± 1/4"
4. PUMP RATING AND TANK CAPACITY ARE SHOWN AS NOMINAL VALUES. THE ACTUAL VALUES MAY VARY.
5. CHASSIS GVWR SHOWN IS THE MINIMUM REQUIRED FOR STANDARD BODY DEPENDING OF OPTIONS, GVWR MAY NEED TO BE INCREASED.
6. COMMERCIAL OEM CAB STEPS MAY NOT MEET UL STANDARD. SELECT CUSTOM STEPS WHEN REQUIRED
7. OVERALL HEIGHT IS IN LOADED CONDITION, UNLOADED HEIGHT MAY BE 4" ABOVE HEIGHT SHOWN. AFTER TRUCK IS COMPLETED ADDITIONAL STEPS MAY BE REQUIRED TO MEET THE STANDARD.
8. DIMENSIONS SHOWN ARE APPROXIMATE AND ARE SUBJECT TO CHANGE AS MAY BE FOUND NECESSARY DURING DESIGN. DO NOT SCALE DRAWING.
9. MINOR DETAILS AND REFLECTIVE STRIPING ARE NOT SHOWN.



THIS DRAWING IS PROPERTY OF FORT GARRY FIRE TRUCKS LTD (FGFT) AND MUST NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART, BY ANY METHOD WHATSOEVER, WITHOUT AUTHORIZATION OF FGFT.

REV	DESCRIPTION OF CHANGE	BY	DATE
C	REVISED QUOTE DRAWING	TV	25 FEB 2020
B	REVISED QUOTE DRAWING	TV	22 OCT 2019
A	QUOTE DRAWING	TV	03 SEP 2019

DESCRIPTION: <i>FORESTPORT FIREFIGHTERS INC</i>		
SCALE: 1:50	DWG. BY: TV	CHK. BY:

MODEL: AFT17H3	SHEET: 1 OF 1
DATE: 09 OCT 2019	DWG. NO. : 19PVM05